

NATIONAL BUREAU OF STANDARDS REPORT

5822

PERFORMANCE TESTS OF CAMBRIDGE
"AEROSOLVE" AIR FILTERS
(TYPES 3A-95 & 3A-35)

by

Thomas W. Watson and Henry E. Robinson

Report to
General Services Administration
Public Buildings Service
Washington 25, D. C.



U. S. DEPARTMENT OF COMMERCE
NATIONAL BUREAU OF STANDARDS

THE NATIONAL BUREAU OF STANDARDS

Functions and Activities

The functions of the National Bureau of Standards are set forth in the Act of Congress, March 3, 1901, as amended by Congress in Public Law 619, 1950. These include the development and maintenance of the national standards of measurement and the provision of means and methods for making measurements consistent with these standards; the determination of physical constants and properties of materials; the development of methods and instruments for testing materials, devices, and structures; advisory services to Government Agencies on scientific and technical problems; invention and development of devices to serve special needs of the Government; and the development of standard practices, codes, and specifications. The work includes basic and applied research, development, engineering, instrumentation, testing, evaluation, calibration services, and various consultation and information services. A major portion of the Bureau's work is performed for other Government Agencies, particularly the Department of Defense and the Atomic Energy Commission. The scope of activities is suggested by the listing of divisions and sections on the inside of the back cover.

Reports and Publications

The results of the Bureau's work take the form of either actual equipment and devices or published papers and reports. Reports are issued to the sponsoring agency of a particular project or program. Published papers appear either in the Bureau's own series of publications or in the journals of professional and scientific societies. The Bureau itself publishes three monthly periodicals, available from the Government Printing Office: The Journal of Research, which presents complete papers reporting technical investigations; the Technical News Bulletin, which presents summary and preliminary reports on work in progress; and Basic Radio Propagation Predictions, which provides data for determining the best frequencies to use for radio communications throughout the world. There are also five series of nonperiodical publications: The Applied Mathematics Series, Circulars, Handbooks, Building Materials and Structures Reports, and Miscellaneous Publications.

Information on the Bureau's publications can be found in NBS Circular 460, Publications of the National Bureau of Standards (\$1.25) and its Supplement (\$0.75), available from the Superintendent of Documents, Government Printing Office, Washington 25, D. C.

Inquiries regarding the Bureau's reports should be addressed to the Office of Technical Information, National Bureau of Standards, Washington 25, D. C.

NATIONAL BUREAU OF STANDARDS REPORT

NBS PROJECT

1000-30-4890

NBS REPORT

5822

March 25, 1958

PERFORMANCE TESTS OF CAMBRIDGE "AEROSOLVE" AIR FILTERS (TYPES 3A-95 & 3A-35)

by

Thomas W. Watson and Henry E. Robinson

Heat Transfer Section
Building Technology Division

Report to
General Services Administration
Public Buildings Service
Washington 25, D. C.

IMPORTANT NOTICE

NATIONAL BUREAU OF STANDARDS
Intended for use within the Government
to additional evaluation and re-
listing of this Report, either in
the Office of the Director, National
however, by the Government a
to reproduce additional copies

Approved for public release by the
Director of the National Institute of
Standards and Technology (NIST)
on October 9, 2015.

Progress accounting documents
nally published it is subjected
reproduction, or open-literature
ion is obtained in writing from
Such permission is not needed,
prepared if that agency wishes



U. S. DEPARTMENT OF COMMERCE
NATIONAL BUREAU OF STANDARDS

PERFORMANCE TESTS OF TYPES 3A-95 AND 3A-35 CAMBRIDGE "AEROSOLVE" AIR FILTERS

by

Thomas W. Watson and Henry E. Robinson

1. INTRODUCTION*

At the request of the Public Buildings Service, General Services Administration, the performance characteristics of dry-type air filters were determined to provide information to assist in the preparation of air filter specifications.

The test results presented herein were obtained on specimen dry-type air filters submitted by the manufacturer at the request of the Public Buildings Service, and included determinations of dust-arresting efficiency with two aerosols (atmospheric air and Cottrell precipitate), pressure drop, and dirt loading performance.

2. DESCRIPTION OF THE FILTER SPECIMENS

The two filters submitted were manufactured by the Cambridge Filter Corporation of Syracuse, New York, and were dry-type, replaceable cartridge, air filters, 24x24x12 inches in nominal size. They were identified by the manufacturer as Aerosolve Model 3A-95 and Aerosolve Model 3A-35 cartridges.

A permanent steel frame (Cambridge Model 4A-1000) was furnished for holding the replaceable cartridges during use. This frame had overall dimensions of 23 15/16 x 23 15/16 x 12 inches.

The Model 3A-95 replaceable air filter cartridge had overall dimensions of 23 3/8 x 23 3/8 x 12 inches. The filtering media consisted of a mat or blanket about 3/8 inch thick of apparently un-oiled fine glass fibers, reportedly approximately one micron in diameter. In the cartridge, the blanket was arranged in pleats or vee-folds over wires at the end of the vees, and its edges were glued to the surrounding frame of fire-resistant two-ply corrugated paperboard.

*This report is submitted for information only, and is not released for use in connection with advertising or sales promotion.

The downstream face of the media was supported by a thin glass fiber sheet. Insertion of the replacement cartridge in the permanent steel frame additionally reinforces and supports the filter media by means of wire vees permanently installed in the steel frame. The inside edge of the replacement cartridge is pressed against a felt gasket in the steel frame to effect a dust-tight seal. The net face area of the filter was 3.60 sq. ft., and the area of the blanket effective for filtering was approximately 43 sq. ft.

The Model 3A-35 air filter cartridge was identical in size and design, except that the glass fiber blanket was of coarser texture, the glass fibers having a diameter of approximately 3 microns.

3. TEST METHOD AND PROCEDURE

Efficiency determinations were made by the NBS "Dust-Spot Method" using the following aerosols: (a) outdoor atmospheric air drawn through the laboratory without addition of other dust or contaminant; and (b) Cottrell precipitate dispersed in the outdoor atmospheric air. The test method is described in a paper "A Test Method for Air Filters" by R. S. Dill (ASHVE Transactions, Vol. 44, p. 379, 1938).

For these tests, the filter was installed in the apparatus and the desired rate of air flow through the cleaner was established. Samples of air were drawn from the center of the test duct, at points one foot upstream and eight feet downstream of the filter and passed through known areas of Whatman No. 41 filter paper. The areas of the filter paper used upstream and downstream and the times during which the air was sampled upstream and downstream were selected experimentally so that the change in transmission of light through the two filter paper spots would be about the same. The filter efficiency was calculated by means of the formula

$$\text{Efficiency, percent} = 100 \left[1 - \frac{A_2}{A_1} \cdot \frac{O_2}{O_1} \cdot \frac{T_1}{T_2} \right]$$

where A represents the dust spot area, O the change in light transmittance of the filter paper as measured before and after the deposition of dust, and T the time during which the air sample was drawn. Subscripts 1 and 2 refer to the upstream and downstream positions, respectively.

Two efficiency-measuring techniques, or modifications based on the above formula, were used, depending on the apparent efficiency of the filter with the different aerosols.

For the tests made, techniques L and N were used, as indicated in Table 2.

All light transmission measurements were made with the photometer illumination at a constant intensity, as determined by measurement on a reference of constant transmission characteristics. The filter papers used upstream and downstream were selected to have equal light transmissions when clean.

The efficiency of the filter in arresting particulate matter in atmospheric air was determined by means of tests of the L type, as described in Table 2, with the filter clean. Following these, the efficiency of the filter in arresting Cottrell precipitate was measured by means of two N-type tests, after which was begun the process of loading the filter with a mixture of 4 percent cotton lint and 96 percent of Cottrell precipitate, by weight, separately dispersed in the air stream. The lint used for this purpose was No. 7 cotton linters previously ground in a Wiley mill with a 4-millimeter screen. At suitable periods, as the loading progressed, the efficiency of the filter was determined using Cottrell precipitate in outdoor air. Pressure drops were recorded at intervals during the test. The dirt-loading was continued until the pressure drop increased to approximately 0.90 inch W.G. for the 3A-95 filter, and 0.57 inch W.G. for the 3A-35 filter. The efficiency was again determined with Cottrell precipitate and then with atmospheric air as the aerosols.

4. TEST RESULTS

Table 1 presents data as to the pressure drops of the clean filters at several rates of air flow.

The performance of the filters at 1000 cfm is summarized in Table 2, and is also shown graphically in Figures 1 and 2 for both aerosols A and C.

Observation of the filters at the end of the dirt-loading tests showed that the lint fraction of the dirt-load was uniformly deposited on the upstream faces, and had not penetrated appreciably into the media. In the case of the 3A-95 filter, the bulk of the dust fraction of the dirt load was found on the upstream face and had not penetrated into the media beyond about 1/16-inch. The downstream face of this filter was observed to be clean and not discolored. In the case of the 3A-35 filter, the downstream face of the media was uniformly darkened at the end of the dirt-loading test. No lint was visible on the downstream face of either filter.

TABLE 1
PRESSURE DROP OF CLEAN FILTERS

<u>Air Flow</u> cfm	<u>Face Velocity</u> fpm	<u>Pressure Drop</u> inch W.G.
<hr/> 3A-95 <hr/>		
1200	28	0.507
1000	23	.414
800	19	.322
600	14	.234
<hr/> 3A-35 <hr/>		
1200	28	0.172
1000	23	.133
800	19	.094
600	14	.063

TABLE 2

PERFORMANCE OF FILTERS AT 1000 CFM


<u>Filter</u>	<u>Aerosol(1)</u>	<u>Total Dirt Load(2) grams</u>	<u>Pressure Drop inch W.G.</u>	<u>Eff. Meas. Technique(3)</u>	<u>Efficiency percent</u>
3A-95	A	-	0.422	L	92.0
		-	.423	L	91.4
		-	.428	L	90.8
		-	.438	L	91.2
					Avg. 91.4
	C	10	.438	N	99.7
		19	.438	N	99.7
		306	.503	N	99.9
		415	.543	-	-
		533	.603	N	99.9
		692	.705	-	-
		811	.797	-	-
		909	.865	N	99.8
	A	909	.910	L	98.8
		909	.918	L	97.7
3A-35	A	-	.130	L	24.0
		-	.130	L	23.4
		-	.130	L	23.8
	C	10	.132	N	85.1
		19	.133	N	90.5
		29	.136	N	93.9
		38	.137	N	94.7
	A	59	.140	L	37.7
		59	.140	L	38.4
	C	257	.160	-	-
		374	.176	-	-
		542	.200	N	94.1
		790	.242	-	-
		956	.299	N	95.7
		1145	.372	-	-
		1235	.406	N	96.2
		1384	.450	-	-
		1453	.503	N	97.8
		1684	.558	-	-
		1813	.605	N	96.9
		1822	.612	N	96.9
	A	1822	.580	L	63.1
		1822	.570	L	62.8

(Cont'd)

TABLE 2 (Cont'd)

- (1) Aerosol A: Particulate matter in atmospheric air at NBS
Aerosol C: Cottrell precipitate in atmospheric air (1 gram per 1000 cf).
- (2) Average mixture: 3.9 percent lint, 96.1 percent Cottrell precipitate, by weight.
- (3) Efficiency measuring technique:
 - L: Air sampled at equal rates through equal areas; upstream sampling time selected to yield approximately equal dust-spot opacities of the upstream and downstream filter papers.
 - N: Air sampled at equal rates for equal times; downstream areas selected to yield approximately equal dust-spot opacities of the upstream and downstream filter papers.

MODEL 3A-95



MODEL 3A-35




FIG. 2

U. S. DEPARTMENT OF COMMERCE

Sinclair Weeks, *Secretary*

NATIONAL BUREAU OF STANDARDS

A. V. Astin, *Director*



THE NATIONAL BUREAU OF STANDARDS

The scope of activities of the National Bureau of Standards at its headquarters in Washington, D. C., and its major laboratories in Boulder, Colo., is suggested in the following listing of the divisions and sections engaged in technical work. In general, each section carries out specialized research, development, and engineering in the field indicated by its title. A brief description of the activities, and of the resultant publications, appears on the inside front cover.

WASHINGTON, D. C.

Electricity and Electronics. Resistance and Reactance. Electron Devices. Electrical Instruments. Magnetic Measurements. Dielectrics. Engineering Electronics. Electronic Instrumentation. Electrochemistry.

Optics and Metrology. Photometry and Colorimetry. Optical Instruments. Photographic Technology. Length. Engineering Metrology.

Heat. Temperature Physics. Thermodynamics. Cryogenic Physics. Rheology. Engine Fuels. Free Radicals Research.

Atomic and Radiation Physics. Spectroscopy. Radiometry. Mass Spectrometry. Solid State Physics. Electron Physics. Atomic Physics. Neutron Physics. Nuclear Physics. Radioactivity. X-rays. Betatron. Nucleonic Instrumentation. Radiological Equipment.

Chemistry. Organic Coatings. Surface Chemistry. Organic Chemistry. Analytical Chemistry. Inorganic Chemistry. Electrodeposition. Molecular Structure and Properties of Gases. Physical Chemistry. Thermochemistry. Spectrochemistry. Pure Substances.

Mechanics. Sound. Mechanical Instruments. Fluid Mechanics. Engineering Mechanics. Mass and Scale. Capacity, Density, and Fluid Meters. Combustion Controls.

Organic and Fibrous Materials. Rubber. Textiles. Paper. Leather. Testing and Specifications. Polymer Structure. Plastics. Dental Research.

Metallurgy. Thermal Metallurgy. Chemical Metallurgy. Mechanical Metallurgy. Corrosion. Metal Physics.

Mineral Products. Engineering Ceramics. Glass. Refractories. Enameled Metals. Concreting Materials. Constitution and Microstructure.

Building Technology. Structural Engineering. Fire Protection. Air Conditioning, Heating, and Refrigeration. Floor, Roof, and Wall Coverings. Codes and Safety Standards. Heat Transfer.

Applied Mathematics. Numerical Analysis. Computation. Statistical Engineering. Mathematical Physics.

Data Processing Systems. SEAC Engineering Group. Components and Techniques. Digital Circuitry. Digital Systems. Analog Systems. Application Engineering.

• Office of Basic Instrumentation.

• Office of Weights and Measures.

BOULDER, COLORADO

Cryogenic Engineering. Cryogenic Equipment. Cryogenic Processes. Properties of Materials. Gas Liquefaction.

Radio Propagation Physics. Upper Atmosphere Research. Ionospheric Research. Regular Propagation Services. Sun-Earth Relationships. VHF Research.

Radio Propagation Engineering. Data Reduction Instrumentation. Modulation Systems. Navigation Systems. Radio Noise. Tropospheric Measurements. Tropospheric Analysis. Radio Systems Application Engineering. Radio Meteorology.

Radio Standards. High Frequency Electrical Standards. Radio Broadcast Service. High Frequency Impedance Standards. Calibration Center. Microwave Physics. Microwave Circuit Standards.

